DETAILED ESTIMATE

DETAILED ESTIMATE

For the Work of

"Improvements And Restoration Of Roads At Shivapura, Babanagara, Kempegowda Layout, Durgamba Layout Of Kattigenahalli Village And Other Roads In Ward No.05 Byatarayanapura Sub Division"

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- IMPROVEMENTS AND RESTORATION OF ROADS AT SHIVAPURA, BABANAGARA, KEMPEGOWDA LAYOUT, DURGAMBA LAYOUT OF KATTIGENAHALLI VILLAGE AND OTHER ROADS IN WARD NO.05 BYATARAYANAPURA SUB DIVISION

								Estimation Cost.Rs	**10000000.00**
Sl No	**Description of work**		**Mesurement**				**Qty**	**Rate**	**Amount**
		Unit	**No.**	**L**	**B**	**D**			
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80								
	Drain Desilting								
	Saralaya layout								
	Main Road (W0339)	Cum	2	92.00	0.45	0.45	37.26		
	(W0341)	Cum	2	205.00	0.45	0.45	83.03		
	(W0341)	Cum	2	208.00	0.45	0.45	84.24		
	Connecting Road	Cum	2	37.00	0.45	0.45	14.99		
	Kattigenahalli Over Head Tank								
	1st B Cross Road (W0311)	Cum	2	160.00	0.45	0.45	64.80		
	1st B Cross Road	Cum	2	41.00	0.45	0.45	16.61		
	Kalidasa Layout								
	Cross Road-1	Cum	1	86.00	0.45	0.45	17.42		
	(W0331)	Cum	2	127.00	0.60	0.60	91.44		
	(W0265)	Cum	2	145.00	0.60	0.60	104.40		
	Over Burden								
	Manjunath Layout								
	(W0265)	Cum	1	15.00	1.50	0.60	13.50		
	Basic rate	130.00							
	Area weightage 6%	7.80							
	5Km lead & Lift= 57+(2*1.28*5)	69.80							
	Sub Total	**207.60**							
	Total						**527.67**	**207.60**	**109544.00**
2	**Removing and refixing** stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33)								
	BS slab of Drain								
	Open Drain (Sides & Bottom)		Width=Perimeter of Drain in U Shape						
	Saralaya layout								
	Main Road (W0339)	Sqm	2	92.00	1.35		248.40		
	(W0341)	Sqm	2	205.00	1.35		553.50		
	(W0341)	Sqm	2	208.00	1.35		561.60		
	Connecting Road	Sqm	2	37.00	1.35		99.90		
	Kattigenahalli Over Head Tank								
	1st B Cross Road (W0311)	Sqm	2	160.00	1.35		432.00		
	1st B Cross Road	Sqm	2	41.00	1.35		110.70		
	Kalidasa Layout								
	Cross Road-1	Sqm	1	86.00	1.35		116.10		
	(W0331)	Sqm	2	127.00	1.80		457.20		

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	Manjunath Layout								
	(W0265)	Sqm	2	145.00	1.80		522.00		
					Total		**3101.40**		
	Deduct 30% for Missing/Damaged						**930.42**		
	Consider 70% Qnty for Removing & Refixing						**2170.98**		
	Basic rate	105.00							
	Area weightage 6%	6.3							
	Sub Total	**111.30**							
	Total						**2170.98**	**111.30**	**241630.00**
3	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.(P.No.27,I.No.5.31.1)								
	Provide30% new BS Slab for Missing/Damaged	From item no.2					**930.42**		
	Basic rate	700.00							
	Area weightage 6%	42							
	Sub Total	**742.00**							
	Total						**930.42**	**742.00**	**690371.00**
4	KSRRB M300-14. **Excavation for roadwork in all types of soil** by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 5km lead= (I No-19.14,P No-143)								
	Road Cut Portion								
	Kattigenahalli Over Head Tank								
	1st B Cross Road (W0311)	Cum	1	160.00	0.75	0.20	24.00		
		Cum	1	10.00	0.60	0.20	1.20		
		Cum	1	15.00	0.75	0.20	2.25		
		Cum	1	10.00	1.00	0.20	2.00		
	1st B Cross Road	Cum	1	41.00	0.60	0.20	4.92		
		Cum	1	10.00	1.00	0.20	2.00		
	Saralaya layout								
	Main Road (W0339)	Cum	1	10.00	2.00	0.20	4.00		
		Cum	1	15.00	0.60	0.20	1.80		
		Cum	1	6.00	1.00	0.20	1.20		
	Kalidasa Layout								
	Main Road (W0090)	Cum	1	20.00	1.50	0.20	6.00		
		Cum	1	10.00	0.90	0.20	1.80		
		Cum	1	8.00	1.20	0.20	1.92		
	Basic rate	41.00							
	Area weightage 6%	2.46							
	5Km lead= (2*1.28*5)	12.80							
	Sub Total	**56.26**							
	Total						**53.09**	**56.26**	**2986.00**

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
5	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications. MORTH / Chapter 3(P.No.146, I.No.19.56)								
	Saralaya layout								
	(W0341)	Sqm	1	205.00	5.80		1189.00		
	(W0341)	Sqm	1	208.00	6.00		1248.00		
	Connecting Road	Sqm	1	37.00	6.00		222.00		
	Kalidasa Layout								
	Cross Road-1	Sqm	1	86.00	4.60		395.60		
	(W0331)	Sqm	1	127.00	6.00		762.00		
	Manjunath Layout								
	1st Cross Road (W0261)	Sqm	1	128.00	7.40		947.20		
	(W0265)	Sqm	1	145.00	6.40		928.00		
	Basic rate	39.00							
	Area weightage 6%	2.34							
	Sub Total	**41.34**							
	Total						**5691.80**	**41.34**	**235299.00**
6	KSRRB 300-58. **Compaction of original ground** by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147)								
	Road								
	Saralaya layout								
	(W0341)	Sqm	1	205.00	5.80		1189.00		
	(W0341)	Sqm	1	208.00	6.00		1248.00		
	Connecting Road	Sqm	1	37.00	6.00		222.00		
	Kalidasa Layout								
	Cross Road-1	Sqm	1	86.00	4.60		395.60		
	(W0331)	Sqm	1	127.00	6.00		762.00		
	Manjunath Layout								
	1st Cross Road (W0261)	Sqm	1	128.00	7.40		947.20		
	(W0265)	Sqm	1	145.00	6.40		928.00		
	Basic rate	6.00							
	Area weightage 6%	0.36							
	Sub Total	**6.36**							
	Total						**5691.80**	**6.36**	**36199.00**
7	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	Saralaya layout								
	(W0341)	Cum	1	205.00	5.80	0.20	237.80		
	(W0341)	Cum	1	208.00	6.00	0.20	249.60		
	Connecting Road	Cum	1	37.00	6.00	0.20	44.40		
	Kalidasa Layout								
	Cross Road-1	Cum	1	86.00	4.60	0.20	79.12		
	(W0331)	Cum	1	127.00	6.00	0.20	152.40		
	Manjunath Layout								
	(W0261)	Cum	1	128.00	7.40	0.20	189.44		
	(W0265)	Cum	1	145.00	6.40	0.20	185.60		

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	Road Cut Portion								
	Kattigenahalli Over Head Tank								
	1st B Cross Road (W0311)	Cum	1	160.00	0.75	0.20	24.00		
		Cum	1	10.00	0.60	0.20	1.20		
		Cum	1	15.00	0.75	0.20	2.25		
		Cum	1	10.00	1.00	0.20	2.00		
	1st B Cross Road	Cum	1	41.00	0.60	0.20	4.92		
		Cum	1	10.00	1.00	0.20	2.00		
	Saralaya layout								
	Main Road (W0339)	Cum	1	10.00	2.00	0.20	4.00		
		Cum	1	15.00	0.60	0.20	1.80		
		Cum	1	6.00	1.00	0.20	1.20		
	Kalidasa Layout								
	Main Road (W0090)	Cum	1	20.00	1.50	0.20	6.00		
		Cum	1	10.00	0.90	0.20	1.80		
		Cum	1	8.00	1.20	0.20	1.92		
	Basic rate	1888.00							
	Area weightage 6%	113.28							
	Sub Total	**2001.28**							
	Total						**1191.45**	**2001.28**	**2384425.00**
9	KSRRB M500-6. Providing and applying **primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6)								
	Saralaya layout								
	(W0341)	Sqm	1	205.00	5.80		1189.00		
	(W0341)	Sqm	1	208.00	6.00		1248.00		
	Connecting Road	Sqm	1	37.00	6.00		222.00		
	Kalidasa Layout								
	Cross Road-1	Sqm	1	86.00	4.60		395.60		
	(W0331)	Sqm	1	127.00	6.00		762.00		
	Manjunath Layout								
	1st Cross Road (W0261)	Sqm	1	128.00	7.40		947.20		
	(W0265)	Sqm	1	145.00	6.40		928.00		
	Road Cut Portion								
	Kattigenahalli Over Head Tank								
	1st B Cross Road (W0311)	Sqm	1	160.00	0.75		120.00		
		Sqm	1	10.00	0.60		6.00		
		Sqm	1	15.00	0.75		11.25		
		Sqm	1	10.00	1.00		10.00		
	1st B Cross Road	Sqm	1	41.00	0.60		24.60		
		Sqm	1	10.00	1.00		10.00		
	Saralaya layout								
	Main Road (W0339)	Sqm	1	10.00	2.00		20.00		
		Sqm	1	15.00	0.60		9.00		
		Sqm	1	6.00	1.00		6.00		
	Kalidasa Layout								
	Main Road (W0090)	Sqm	1	20.00	1.50		30.00		
		Sqm	1	10.00	0.90		9.00		

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
		Sqm	1	8.00	1.20		9.60		
	Basic rate	32.00							
	Area weightage 6%	1.92							
	Sub Total	**33.92**							
	Total						**5957.25**	**33.92**	**202070.00**
10	KSRRB 500-11. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 3.4 % VG-30 Bitumen(P.No.159,I.No.21.11.6).								
	Saralaya layout								
	(W0341)	Cum	1	205.00	5.80	0.05	59.45		
	(W0341)	Cum	1	208.00	6.00	0.05	62.40		
	Connecting Road	Cum	1	37.00	6.00	0.05	11.10		
	Kalidasa Layout								
	Cross Road-1	Cum	1	86.00	4.60	0.05	19.78		
	(W0331)	Cum	1	127.00	6.00	0.05	38.10		
	Manjunath Layout								
	1st Cross Road (W0261)	Cum	1	128.00	7.40	0.05	47.36		
	(W0265)	Cum	1	145.00	6.40	0.05	46.40		
	Road Cut Portion								
	Kattigenahalli Over Head Tank								
	1st B Cross Road (W0311)	Cum	1	160.00	0.75	0.05	6.00		
		Cum	1	10.00	0.60	0.05	0.30		
		Cum	1	15.00	0.75	0.05	0.56		
		Cum	1	10.00	1.00	0.05	0.50		
	1st B Cross Road	Cum	1	41.00	0.60	0.05	1.23		
		Cum	1	10.00	1.00	0.05	0.50		
	Saralaya layout								
	Main Road (W0339)	Cum	1	10.00	2.00	0.05	1.00		
		Cum	1	15.00	0.60	0.05	0.45		
		Cum	1	6.00	1.00	0.05	0.30		
	Kalidasa Layout								
	Main Road (W0090)	Cum	1	20.00	1.50	0.05	1.50		
		Cum	1	10.00	0.90	0.05	0.45		
		Cum	1	8.00	1.20	0.05	0.48		
	Basic rate	5533.00							
	Area weightage 6%	331.98							
	Sub Total	**5864.98**							
	Total						**297.86**	**5864.98**	**1746958.00**
11	KSRRB 500-2.Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications.(P.No.158,I.No.21.2).								
	Kattigenahalli Over Head Tank								
	1st B Cross Road (W0311)	Sqm	1	160.00	5.20		832.00		

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	1st B Cross Road	Sqm	1	41.00	4.90		200.90		
	Saralaya layout								
	Main Road (W0339)	Sqm	1	92.00	7.30		671.60		
	Kalidasa Layout								
	Main Road (W0090)	Sqm	1	188.00	5.50		1034.00		
	Basic rate	5.00							
	Area weightage 6%	0.3							
	Sub Total	**5.30**							
	Total						**2738.50**	**5.30**	**14515.00**
12	KSRRB 500-7. Providing and **applying tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7) issue Rate								
	Saralaya layout								
	Main Road (W0339)	Sqm	1	92.00	7.30		671.60		
	(W0341)	Sqm	1	205.00	5.80		1189.00		
	(W0341)	Sqm	1	208.00	6.00		1248.00		
	Connecting Road	Sqm	1	37.00	6.00		222.00		
	Kattigenahalli Over Head Tank								
	1st B Cross Road (W0311)	Sqm	1	160.00	5.20		832.00		
	1st B Cross Road	Sqm	1	41.00	4.90		200.90		
	Kalidasa Layout								
	Main Road (W0090)	Sqm	1	188.00	5.50		1034.00		
	Cross Road-1	Sqm	1	86.00	4.60		395.60		
	(W0331)	Sqm	1	127.00	6.00		762.00		
	Manjunath Layout								
	1st Cross Road (W0261)	Sqm	1	128.00	7.40		947.20		
	(W0265)	Sqm	1	145.00	6.40		928.00		
	Basic rate	12.00							
	Area weightage 6%	0.72							
	Sub Total	**12.72**							
	Total						**8430.30**	**12.72**	**107234.00**
13	KSRRB M500-19. Providing and laying **bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 507 of MORTH V revision using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-ll (30 mm to 45 mm) with 5.4% VG-30 Bitumen(P.No-162,I No-21.22.6)								
	Saralaya layout								
	Main Road (W0339)	Cum	1	92.00	7.30	0.04	26.86		
	(W0341)	Cum	1	205.00	5.80	0.04	47.56		
	(W0341)	Cum	1	208.00	6.00	0.04	49.92		
	Connecting Road	Cum	1	37.00	6.00	0.04	8.88		
	Kattigenahalli Over Head Tank								
	1st B Cross Road (W0311)	Cum	1	160.00	5.20	0.04	33.28		
	1st B Cross Road	Cum	1	41.00	4.90	0.04	8.04		
	Kalidasa Layout								
	Main Road (W0090)	Cum	1	188.00	5.50	0.04	41.36		
	Cross Road-1	Cum	1	86.00	4.60	0.04	15.82		
	(W0331)	Cum	1	127.00	6.00	0.04	30.48		

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	Manjunath Layout								
	1st Cross Road (W0261)	Cum	1	128.00	7.40	0.04	37.89		
	(W0265)	Cum	1	145.00	6.40	0.04	37.12		
	Basic rate	7972.00							
	Area weightage 6%	478.32							
	Sub Total	**8450.32**							
	Total						**337.21**	**8450.32**	**2849550.00**
14	KSRRB M800-13.**Road Marking with Hot Applied Thermoplastic Compound** with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)								
	Saralaya layout	Sqm							
	Main Road (W0339)	Sqm	2	92.00	0.10		18.40		
	(W0341)	Sqm	2	205.00	0.10		41.00		
	(W0341)	Sqm	2	208.00	0.10		41.60		
	Connecting Road	Sqm	2	37.00	0.10		7.40		
	Kattigenahalli Over Head Tank								
	1st B Cross Road (W0311)	Sqm	2	160.00	0.10		32.00		
	1st B Cross Road	Sqm	2	41.00	0.10		8.20		
	Kalidasa Layout								
	Main Road (W0090)	Sqm	2	188.00	0.10		37.60		
	Cross Road-1	Sqm	2	86.00	0.10		17.20		
	(W0331)	Sqm	2	127.00	0.10		25.40		
	Manjunath Layout								
	1st Cross Road (W0261)	Sqm	2	128.00	0.10		25.60		
	(W0265)	Sqm	2	145.00	0.10		29.00		
	Basic rate	429.00							
	Area weightage 6%	25.74							
	Sub Total	**454.74**							
	Total						**283.40**	**454.74**	**128874.00**
								Grand Total	**8749655.00**
								GST Charges (12% of estimated cost)	**1049958.00**
								DPR Charges (1% of estimated cost)	**100000.00**
								Project management And Consultancy Charges(1% of estimated cost)	**100000.00**
								Miscellenious and rounding	**387.00**
								Total Amount	**10000000.00**
									RUPEES ONE CRORE ONLY

CERTIFICATE:

1) The work spot has been inspected and found to be necessary
2) The work spot comes under B.B.M.P
3) The provisions made in the estimate are necessary and minimum
4) The estimate is based on C.S.R of 2018-2019,Issue rates and Data Rates.

Assistant Engineer
BBMP

RUDRAPRASAD CONSULTANTS BANGALORE

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

DETAILED ESTIMATE

For the Work of

"Improvements And Restoration Of Roads At M.S Nagara, Thirumenahalli Lake Road, Cross Roads And Main Road Of Thirumenahalli Village And Other Roads In Ward No. 05 Byatarayanapura Sub Division"

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- IMPROVEMENTS AND RESTORATION OF ROADS AT M.S NAGARA, THIRUMENAHALLI LAKE ROAD, CROSS ROADS AND MAIN ROAD OF THIRUMENAHALLI VILLAGE AND OTHER ROADS IN WARD NO. 05 BYATARAYANAPURA SUB DIVISION

									Estimation Cost.Rs	**10000000.00**
Sl No	**Description of work**		**Mesurement**				**Qty**	**Rate**	**Amount**	
		Unit	**No.**	**L**	**B**	**D**				
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80									
	Drain Desilting									
	MS Nagar									
	3rd Cross Road (W1161)	Cum	2	284.00	0.60	0.60	204.48			
	Cross Road (W1163)	Cum	2	95.50	0.60	0.60	68.76			
	Arun Shelters (W1165)	Cum	2	198.00	0.60	0.60	142.56			
	5th Cross Road (W1153)	Cum	2	54.00	0.60	0.60	38.88			
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Cum	2	396.00	0.45	0.45	160.38			
	Culvert									
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Cum	1	10.00	1.70	1.85	31.45			
		Cum	1	6.00	1.40	0.95	7.98			
	Basic rate	130.00								
	Area weightage 6%	7.80								
	5Km lead & Lift= 57+(2*1.28*5)	69.80								
	Sub Total	**207.60**								
	Total						**654.49**	**207.60**	**135872.00**	
2	**Removing and refixing** stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33)									
	BS slab of Drain									
	Open Drain (Sides & Bottom)		Width=Perimeter of Drain in U Shape							
	MS Nagar									
	3rd Cross Road (W1161)	Sqm	2	284.00	1.80		1022.40			
	Cross Road (W1163)	Sqm	2	95.50	1.80		343.80			
	Arun Shelters (W1165)	Sqm	2	198.00	1.80		712.80			
	5th Cross Road (W1153)	Sqm	2	54.00	1.80		194.40			

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Sqm	2	396.00	1.35		1069.20		
						Total	**3342.60**		
	Deduct 30% for Missing/Damaged						**1002.78**		
	Consider 70% Qnty for Removing & Refixing						**2339.82**		
	Basic rate	105.00							
	Area weightage 6%	6.3							
	Sub Total	**111.30**							
	Total						**2339.82**	**111.30**	**260422.00**
3	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.(P.No.27,I.No.5.31.1)								
	Provide30% new BS Slab for Missing/Damaged	Sqm	From item no.2				**1002.78**		
	Basic rate	700.00							
	Area weightage 6%	42							
	Sub Total	**742.00**							
	Total						**1002.78**	**742.00**	**744063.00**
4	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.3)								
	For Culvert								
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Cum	1	10.00	1.70	0.15	2.55		
		Cum	1	6.00	1.40	0.15	1.26		
	Basic rate	5301.69							
	Area weightage 6%	318.10							
	Sub Total	**5619.79**							
	Total						**3.81**	**5619.79**	**21412.00**
5	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM complete as per Specification-WALL & Bottom thickness 15Cm(Item No 37.59.2 page no 271)								
	Culvert								
	Bottom Raft								
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Cum	1	10.00	1.50	0.20	3.00		

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
		Cum	1	6.00	1.20	0.20	1.44		
	Side Wall								
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Cum	2	10.00	0.20	1.50	6.00		
		Cum	2	6.00	0.20	0.60	1.44		
						Sub Total	**11.88**		
	Basic rate	7002.82							
	Area weightage 6%	420.17							
	Sub Total	**7422.99**							
	Total						**11.88**	**7422.99**	**88186.00**
6	KSRB M2200-6 Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200Specification No. Pg No.229 Item No.28.8.2								
	For Culvert	Cum	From Item Number.05				11.88		
		kg	Steel assumed 90 Kg/Cum of Concrete				1069.20		
		tonne					**1.07**		
	Basic rate	75610							
	Area weightage 6%	4536.6							
	Sub Total	**80146.60**							
	Total						**1.07**	**80146.60**	**85693.00**
7	Providing and Fixing pre cast **covering Slab 250mm thick** made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge								
	Culver cover Slab								
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Sqm	1	10.00	1.50		15.00		
		Sqm	1	6.00	1.20		7.20		
	Data rate	**5418.00**							
	Total						**22.20**	**5418.00**	**120280.00**
8	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications. MORTH / Chapter 3(P.No.146, I.No.19.56)								
	MS Nagar								
	3rd Cross Road (W1161)	Sqm	1	284.00	7.50		2130.00		
	Cross Road (W1163)	Sqm	1	95.50	4.60		439.30		
	Arun Shelters (W1165)	Sqm	1	198.00	5.90		1168.20		
	5th Cross Road (W1153)	Sqm	1	54.00	7.40		399.60		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Sqm	1	396.00	5.70		2257.20		
	Basic rate	39.00							
	Area weightage 6%	2.34							
	Sub Total	**41.34**							
	Total						**6394.30**	**41.34**	**264340.00**
9	KSRRB 300-58. **Compaction of original ground** by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147)								
	MS Nagar								
	3rd Cross Road (W1161)	Sqm	1	284.00	7.50		2130.00		
	Cross Road (W1163)	Sqm	1	95.50	4.60		439.30		
	Arun Shelters (W1165)	Sqm	1	198.00	5.90		1168.20		
	5th Cross Road (W1153)	Sqm	1	54.00	7.40		399.60		
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Sqm	1	396.00	5.70		2257.20		
	Basic rate	6.00							
	Area weightage 6%	0.36							
	Sub Total	**6.36**							
	Total						**6394.30**	**6.36**	**40667.00**
10	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	MS Nagar								
	3rd Cross Road (W1161)	Cum	1	284.00	7.50	0.20	426.00		
	Cross Road (W1163)	Cum	1	95.50	4.60	0.20	87.86		
	Arun Shelters (W1165)	Cum	1	198.00	5.90	0.20	233.64		
	5th Cross Road (W1153)	Cum	1	54.00	7.40	0.20	79.92		
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Cum	1	396.00	5.70	0.20	451.44		
	Basic rate	1888.00							
	Area weightage 6%	113.28							
	Sub Total	**2001.28**							
	Total						**1278.86**	**2001.28**	**2559356.00**

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
11	KSRRB M500-6. Providing and applying **primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6)								
	MS Nagar								
	3rd Cross Road (W1161)	Sqm	1	284.00	7.50		2130.00		
	Cross Road (W1163)	Sqm	1	95.50	4.60		439.30		
	Arun Shelters (W1165)	Sqm	1	198.00	5.90		1168.20		
	5th Cross Road (W1153)	Sqm	1	54.00	7.40		399.60		
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Sqm	1	396.00	5.70		2257.20		
	Basic rate	32.00							
	Area weightage 6%	1.92							
	Sub Total	**33.92**							
	Total						**6394.30**	**33.92**	**216895.00**
13	KSRRB 500-11. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 3.4 % VG-30 Bitumen(P.No.159,I.No.21.11.6).								
	MS Nagar								
	3rd Cross Road (W1161)	Cum	1	284.00	7.50	0.05	106.50		
	Cross Road (W1163)	Cum	1	95.50	4.60	0.05	21.97		
	Arun Shelters (W1165)	Cum	1	198.00	5.90	0.05	58.41		
	5th Cross Road (W1153)	Cum	1	54.00	7.40	0.05	19.98		
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Cum	1	396.00	5.70	0.05	112.86		
	Basic rate	5533.00							
	Area weightage 6%	331.98							
	Sub Total	**5864.98**							
	Total						**319.72**	**5864.98**	**1875123.00**
14	KSRRB 500-7. Providing and **applying tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7)								
	MS Nagar								
	3rd Cross Road (W1161)	Sqm	1	284.00	7.50		2130.00		
	Cross Road (W1163)	Sqm	1	95.50	4.60		439.30		
	Arun Shelters (W1165)	Sqm	1	198.00	5.90		1168.20		

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	5th Cross Road (W1153)	Sqm	1	54.00	7.40		399.60		
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Sqm	1	396.00	5.70		2257.20		
	Basic rate	12.00							
	Area weightage 6%	0.72							
	Sub Total	**12.72**							
	Total						**6394.30**	**12.72**	**81336.00**
15	KSRRB M500-19. Providing and laying **bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 507 of MORTH V revision using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-ll (30 mm to 45 mm) with 5.4% VG-30 Bitumen(P.No-162,I No-21.22.6)								
	MS Nagar								
	3rd Cross Road (W1161)	Cum	1	284.00	7.50	0.04	85.20		
	Cross Road (W1163)	Cum	1	95.50	4.60	0.04	17.57		
	Arun Shelters (W1165)	Cum	1	198.00	5.90	0.04	46.73		
	5th Cross Road (W1153)	Cum	1	54.00	7.40	0.04	15.98		
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Cum	1	396.00	5.70	0.04	90.29		
	Basic rate	7972.00							
	Area weightage 6%	478.32							
	Sub Total	**8450.32**							
	Total						**255.77**	**8450.32**	**2161356.00**
16	KSRRB M800-13**.Road Marking with Hot Applied Thermoplastic Compound** with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)								
	MS Nagar								
	3rd Cross Road (W1161)	Sqm	2	284.00	0.10		56.80		
	Cross Road (W1163)	Sqm	2	95.50	0.10		19.10		
	Arun Shelters (W1165)	Sqm	2	198.00	0.10		39.60		
	5th Cross Road (W1153)	Sqm	2	54.00	0.10		10.80		
	Chokkanahalli Samasanato Thirumenahalli School (W1299)	Sqm	2	396.00	0.10		79.20		
	Basic rate	429.00							
	Area weightage 6%	25.74							
	Sub Total	**454.74**							
	Total						**205.50**	**454.74**	**93450.00**

Sl No	Description of work		Mesurement				Qty	Rate	Amount
		Unit	No.	L	B	D			
								Grand Total	**8748451.00**
								GST Charges (12% of estimated cost)	**1049815.00**
								DPR Charges (1% of estimated cost)	**100000.00**
								Project management And Consultancy Charges(1% of estimated cost)	**100000.00**
								Miscellenious and rounding	**1734.00**
								Total Amount	**10000000.00**
									RUPEES ONE CRORE ONLY

CERTIFICATE:

1) The work spot has been inspected and found to be necessary
2) The work spot comes under B.B.M.P
3) The provisions made in the estimate are necessary and minimum
4) The estimate is based on C.S.R of 2018-2019,Issue rates and Data Rates.

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

RUDRAPRASAD CONSULTANTS
BANGALORE

DETAILED ESTIMATE

For the Work of

"Improvements And Restoration Of Roads At Chokkanahalli Layout, Green Garden Layout Roads Of Chokkananahalli Village And Other Roads In Wrad No.05 Byatarayanapura Sub Division"

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- IMPROVEMENTS AND RESTORATION OF ROADS AT CHOKKANAHALLI LAYOUT, GREEN GARDEN LAYOUT ROADS OF CHOKKANANAHALLI VILLAGE AND OTHER ROADS IN WRAD NO.05 BYATARAYANAPURA SUB DIVISION

								Estimation Cost.Rs	10000000.00
Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80								
	Drain Desilting								
	Chokkanahalli								
	Green Garden								
	Main Road (WC880)	Cum	2	184.00	0.60	0.60	132.48		
	Cross Road-1 (WA1271)	Cum	2	112.00	0.60	0.60	80.64		
	Cross Road-2 (WB1271)	Cum	2	111.20	0.60	0.60	80.06		
	Cross Road-3	Cum	2	43.00	0.60	0.60	30.96		
	Cross Road-4	Cum	2	100.00	0.60	0.60	72.00		
	Main Road-2	Cum	2	118.00	0.60	0.60	84.96		
	Pyramid Apartment Road	Cum	1	138.00	0.60	0.60	49.68		
	Cross Road-1	Cum	2	130.00	0.60	0.60	93.60		
	Cross Road-3	Cum	2	53.00	0.45	0.45	21.47		
	Balaji Layout	Cum	2	204.00	0.45	0.45	82.62		
	Basic rate	130.00							
	Area weightage 6%	7.80							
	5Km lead & Lift= 57+(2*1.28*5)	69.80							
	Sub Total	**207.60**							
	Total						**728.47**	**207.60**	**151231.00**
2	**Removing and refixing** stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33)								
	BS slab of Drain								
	Open Drain (Sides & Bottom)		Width=Perimeter of Drain in U Shape						
	Chokkanahalli								
	Green Garden								
	Main Road (WC880)	Sqm	2	184.00	1.80		662.40		
	Cross Road-1 (WA1271)	Sqm	2	112.00	1.80		403.20		
	Cross Road-2 (WB1271)	Sqm	2	111.20	1.80		400.32		
	Cross Road-3	Sqm	2	43.00	1.80		154.80		
	Cross Road-4	Sqm	2	100.00	1.80		360.00		
	Main Road-2	Sqm	2	118.00	1.80		424.80		
	Pyramid Apartment Road	Sqm	1	138.00	1.80		248.40		
	Cross Road-1	Sqm	2	130.00	1.80		468.00		
	Cross Road-3	Sqm	2	53.00	1.35		143.10		
	Balaji Layout	Sqm	2	204.00	1.35		550.80		
						Total	**3815.82**		
	Deduct 30% for Missing/Damaged						**1144.75**		
	Consider 70% Qnty for Removing & Refixing						**2671.07**		
	Basic rate	105.00							
	Area weightage 6%	6.3							
	Sub Total	**111.30**							
	Total						**2671.07**	**111.30**	**297290.00**

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
3	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.(P.No.27,I.No.5.31.1)								
	Provide30% new BS Slab for Missing/Damaged	From item no.2					**1144.75**		
	Basic rate	700.00							
	Area weightage 6%	42							
	Sub Total	**742.00**							
	Total						**1144.75**	**742.00**	**849402.00**
4	KSRRB M300-14. **Excavation for roadwork in all types of soil** by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 5km lead= (I No-19.14,P No-143)								
	Road Cut Portion								
	Chokkanahalli								
	Green Garden								
	Cross Road-1 (WA1271)	Cum	1	112.00	0.60	0.20	13.44		
		Cum	1	10.00	1.00	0.20	2.00		
		Cum	1	15.00	0.60	0.20	1.80		
	Pyramid Apartment Road	Cum	1	10.00	2.00	0.20	4.00		
		Cum	1	15.00	1.50	0.20	4.50		
		Cum	1	6.00	1.00	0.20	1.20		
	Cross Road-1	Cum	1	10.00	1.10	0.20	2.20		
		Cum	1	6.00	3.00	0.20	3.60		
		Cum	1	8.00	1.00	0.20	1.60		
	Basic rate	41.00							
	Area weightage 6%	2.46							
	5Km lead= (2*1.28*5)	12.80							
	Sub Total	**56.26**							
	Total						**34.34**	**56.26**	**1932.00**
5	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications. MORTH / Chapter 3(P.No.146, I.No.19.56)								
	Chokkanahalli								
	Green Garden								
	Main Road (WC880)	Sqm	1	184.00	6.70		1232.80		
	Cross Road-2 (WB1271)	Sqm	1	111.20	6.70		745.04		
	Cross Road-3	Sqm	1	43.00	6.70		288.10		
	Cross Road-4	Sqm	1	100.00	6.80		680.00		
	Main Road-2	Sqm	1	118.00	6.40		755.20		
	Cross Road-3	Sqm	1	53.00	6.30		333.90		
	Balaji Layout	Sqm	1	204.00	7.30		1489.20		
	Basic rate	39.00							
	Area weightage 6%	2.34							
	Sub Total	**41.34**							
	Total						**5524.24**	**41.34**	**228372.00**
6	KSRRB 300-58. **Compaction of original ground** by mechanical means including filling in depression occuring during rolling including cost of all labour. HOM complete as per specifications.(I No-19.64,P No-147)								
	Road								
	Chokkanahalli								
	Green Garden								
	Main Road (WC880)	Sqm	1	184.00	6.70		1232.80		
	Cross Road-2 (WB1271)	Sqm	1	111.20	6.70		745.04		
	Cross Road-3	Sqm	1	43.00	6.70		288.10		
	Cross Road-4	Sqm	1	100.00	6.80		680.00		
	Main Road-2	Sqm	1	118.00	6.40		755.20		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Cross Road-3	Sqm	1	53.00	6.30		333.90		
	Balaji Layout	Sqm	1	204.00	7.30		1489.20		
	Basic rate	6.00							
	Area weightage 6%	0.36							
	Sub Total	**6.36**							
	Total						**5524.24**	**6.36**	**35135.00**
7	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	Road								
	Chokkanahalli								
	Green Garden								
	Main Road (WC880)	Cum	1	184.00	6.70	0.20	246.56		
	Cross Road-2 (WB1271)	Cum	1	111.20	6.70	0.20	149.01		
	Cross Road-3	Cum	1	43.00	6.70	0.20	57.62		
	Cross Road-4	Cum	1	100.00	6.80	0.20	136.00		
	Main Road-2	Cum	1	118.00	6.40	0.20	151.04		
	Cross Road-3	Cum	1	53.00	6.30	0.20	66.78		
	Balaji Layout	Cum	1	204.00	7.30	0.20	297.84		
	Road Cut Portion								
	Chokkanahalli								
	Green Garden								
	Cross Road-1 (WA1271)	Cum	1	112.00	0.60	0.20	13.44		
		Cum	1	10.00	1.00	0.20	2.00		
		Cum	1	15.00	0.60	0.20	1.80		
	Pyramid Apartment Road	Cum	1	10.00	2.00	0.20	4.00		
		Cum	1	15.00	1.50	0.20	4.50		
		Cum	1	6.00	1.00	0.20	1.20		
	Cross Road-1	Cum	1	10.00	1.10	0.20	2.20		
		Cum	1	6.00	3.00	0.20	3.60		
		Cum	1	8.00	1.00	0.20	1.60		
	Basic rate	1888.00							
	Area weightage 6%	113.28							
	Sub Total	**2001.28**							
	Total						**1139.19**	**2001.28**	**2279834.00**
8	KSRRB M500-6. Providing and applying **primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6)								
	Road								
	Chokkanahalli								
	Green Garden								
	Main Road (WC880)	Sqm	1	184.00	6.70		1232.80		
	Cross Road-2 (WB1271)	Sqm	1	111.20	6.70		745.04		
	Cross Road-3	Sqm	1	43.00	6.70		288.10		
	Cross Road-4	Sqm	1	100.00	6.80		680.00		
	Main Road-2	Sqm	1	118.00	6.40		755.20		
	Cross Road-3	Sqm	1	53.00	6.30		333.90		
	Balaji Layout	Sqm	1	204.00	7.30		1489.20		
	Road Cut Portion								
	Chokkanahalli								
	Green Garden								
	Cross Road-1 (WA1271)	Sqm	1	112.00	0.60		67.20		
		Sqm	1	10.00	1.00		10.00		
		Sqm	1	15.00	0.60		9.00		
	Pyramid Apartment Road	Sqm	1	10.00	2.00		20.00		

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
		Sqm	1	15.00	1.50		22.50		
		Sqm	1	6.00	1.00		6.00		
	Cross Road-1	Sqm	1	10.00	1.10		11.00		
		Sqm	1	6.00	3.00		18.00		
		Sqm	1	8.00	1.00		8.00		
	Basic rate	32.00							
	Area weightage 6%	1.92							
	Sub Total	**33.92**							
	Total						**5695.94**	**33.92**	**193207.00**
9	KSRRB 500-2.Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications.(P.No.158,I.No.21.2).								
	Road Cut Portion								
	Chokkanahalli								
	Green Garden								
	Cross Road-1 (WA1271)	Sqm	1	112.00	7.50		840.00		
	Pyramid Apartment Road	Sqm	1	138.00	8.90		1228.20		
	Cross Road-1	Sqm	1	130.00	5.60		728.00		
	Basic rate	5.00							
	Area weightage 6%	0.3							
	Sub Total	**5.30**							
	Total						**2796.20**	**5.30**	**14820.00**
10	KSRRB 500-11. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 3.4 % VG-30 Bitumen(P.No.159,I.No.21.11.6).								
	Road								
	Chokkanahalli								
	Green Garden								
	Main Road (WC880)	Cum	1	184.00	6.70	0.05	61.64		
	Cross Road-2 (WB1271)	Cum	1	111.20	6.70	0.05	37.25		
	Cross Road-3	Cum	1	43.00	6.70	0.05	14.41		
	Cross Road-4	Cum	1	100.00	6.80	0.05	34.00		
	Main Road-2	Cum	1	118.00	6.40	0.05	37.76		
	Cross Road-3	Cum	1	53.00	6.30	0.05	16.70		
	Balaji Layout	Cum	1	204.00	7.30	0.05	74.46		
	Road Cut Portion								
	Chokkanahalli								
	Green Garden								
	Cross Road-1 (WA1271)	Cum	1	112.00	0.60	0.05	3.36		
		Cum	1	10.00	1.00	0.05	0.50		
		Cum	1	15.00	0.60	0.05	0.45		
	Pyramid Apartment Road	Cum	1	10.00	2.00	0.05	1.00		
		Cum	1	15.00	1.50	0.05	1.13		
		Cum	1	6.00	1.00	0.05	0.30		
	Cross Road-1	Cum	1	10.00	1.10	0.05	0.55		
		Cum	1	6.00	3.00	0.05	0.90		
		Cum	1	8.00	1.00	0.05	0.40		
	Basic rate	5533.00							
	Area weightage 6%	331.98							
	Sub Total	**5864.98**							
	Total						**284.80**	**5864.98**	**1670329.00**

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
11	KSRRB 500-7. Providing and **applying tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7)								
	Chokkanahalli								
	Green Garden								
	Main Road (WC880)	Sqm	1	184.00	6.70		1232.80		
	Cross Road-1 (WA1271)	Sqm	1	112.00	7.50		840.00		
	Cross Road-2 (WB1271)	Sqm	1	111.20	6.70		745.04		
	Cross Road-3	Sqm	1	43.00	6.70		288.10		
	Cross Road-4	Sqm	1	100.00	6.80		680.00		
	Main Road-2	Sqm	1	118.00	6.40		755.20		
	Pyramid Apartment Road	Sqm	1	138.00	8.90		1228.20		
	Cross Road-1	Sqm	1	130.00	5.60		728.00		
	Cross Road-3	Sqm	1	53.00	6.30		333.90		
	Balaji Layout	Sqm	1	204.00	7.30		1489.20		
	Basic rate	12.00							
	Area weightage 6%	0.72							
	Sub Total	**12.72**					**8320.44**	**12.72**	**105836.00**
	Total								
12	KSRRB M500-19. Providing and laying **bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 507 of MORTH V revision using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-ll (30 mm to 45 mm) with 5.4% VG-30 Bitumen(P.No-162,I No-21.22.6)								
	Chokkanahalli								
	Green Garden								
	Main Road (WC880)	Cum	1	184.00	6.70	0.04	49.31		
	Cross Road-1 (WA1271)	Cum	1	112.00	7.50	0.04	33.60		
	Cross Road-2 (WB1271)	Cum	1	111.20	6.70	0.04	29.80		
	Cross Road-3	Cum	1	43.00	6.70	0.04	11.52		
	Cross Road-4	Cum	1	100.00	6.80	0.04	27.20		
	Main Road-2	Cum	1	118.00	6.40	0.04	30.21		
	Pyramid Apartment Road	Cum	1	138.00	8.90	0.04	49.13		
	Cross Road-1	Cum	1	130.00	5.60	0.04	29.12		
	Cross Road-3	Cum	1	53.00	6.30	0.04	13.36		
	Balaji Layout	Cum	1	204.00	7.30	0.04	59.57		
	Basic rate	7972.00							
	Area weightage 6%	478.32							
	Sub Total	**8450.32**					**332.82**	**8450.32**	**2812416.00**
	Total								
13	KSRRB M800-13.**Road Marking with Hot Applied Thermoplastic Compound** with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)								
	Chokkanahalli								
	Green Garden								
	Main Road (WC880)	Sqm	2	184.00	0.10		36.80		
	Cross Road-1 (WA1271)	Sqm	2	112.00	0.10		22.40		
	Cross Road-2 (WB1271)	Sqm	2	111.20	0.10		22.24		
	Cross Road-3	Sqm	2	43.00	0.10		8.60		
	Cross Road-4	Sqm	2	100.00	0.10		20.00		
	Main Road-2	Sqm	2	118.00	0.10		23.60		
	Pyramid Apartment Road	Sqm	2	138.00	0.10		27.60		
	Cross Road-1	Sqm	2	130.00	0.10		26.00		
	Cross Road-3	Sqm	2	53.00	0.10		10.60		
	Balaji Layout	Sqm	2	204.00	0.10		40.80		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Basic rate	429.00							
	Area weightage 6%	25.74							
	Sub Total	**454.74**							
	Total						**238.64**	**454.74**	**108520.00**
								Grand Total	**8748324.00**
								DPR Charges (1% of estimated cost)	**100000.00**
								Project management And Consultancy Charges(1% of estimated cost)	**100000.00**
								GST Charges (12% of estimated cost)	**1049799.00**
								Miscellenious and rounding	**1877.00**
								Total Amount	**10000000.00**
									RUPEES ONE CRORE ONLY

CERTIFICATE:

1) The work spot has been inspected and found to be necessary
2) The work spot comes under B.B.M.P
3) The provisions made in the estimate are necessary and minimum
4) The estimate is based on C.S.R of 2018-2019,Issue rates and Data Rates.

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

RUDRAPRASAD CONSULTANTS
BANGALORE

DETAILED ESTIMATE

For the Work of

"Improvements And Restoration Of Roads At Palanahalli Roads And Palanahalli Roads And Palanahalli Thota Roads Of Palanahalli Village And Other Roads In Ward No.05 Byatarayanapura Sub Division"

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- IMPROVEMENTS AND RESTORATION OF ROADS AT PALANAHALLI ROADS AND PALANAHALLI ROADS AND PALANAHALLI THOTA ROADS OF PALANAHALLI VILLAGE AND OTHER ROADS IN WARD NO.05 BYATARAYANAPURA SUB DIVISION

								Estimation Cost.Rs	10000000.00
Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80								
	Drain Desilting								
	BS slab of Drain								
	Anand Nagar								
	Cross Road-1 (W0101)	Cum	1	100.00	0.45	0.45	20.25		
	CC Drain								
	Anand Nagar								
	Cross Road-1 (W0101)	Cum	1	100.00	0.50	0.45	22.50		
	1st Cross Road (W0097)	Cum	1	90	0.50	0.50	22.50		
	Defence Layout Ph-1								
	8th Main Road (W0088)	Cum	2	143.00	0.50	0.50	71.50		
	6th Main Road (W0153)	Cum	2	124.00	0.50	0.50	62.00		
	Drain								
	Palanahalli School Road (W0161)	Cum	2	156.00	1.10	0.90	308.88		
	Cross Road	Cum	2	95.00	1.10	0.90	188.10		
	Culvert								
	Palanahalli School Road (W0161)	Cum	1	5.00	1.40	0.95	6.65		
		Cum	2	6.00	1.40	0.95	15.96		
	Basic rate	130.00							
	Area weightage 6%	7.80							
	5Km lead & Lift= 57+(2*1.28*5)	69.80							
	Sub Total	**207.60**							
	Total						**718.34**	**207.60**	**149127.00**
2	**Removing and refixing** stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33)								
	BS slab of Drain								
	Open Drain (Sides & Bottom)		Width=Perimeter of Drain in U Shape						
	Anand Nagar								
	Cross Road-1 (W0101)	Sqm	1	100.00	1.35		135.00		
					Total		**135.00**		
	Deduct 30% for Missing/Damaged						**40.50**		
	Consider 70% Qnty for Removing & Refixing						**94.50**		

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	Precast Cover Slab								
	Anand Nagar								
	Cross Road-1 (W0101)	Sqm	1	100.00	0.90		90.00		
	1st Cross Road (W0097)	Sqm	1	90.00	0.90		81.00		
	Defence Layout Ph-1								
	8th Main Road (W0088)	Sqm	2	143.00	0.90		257.40		
	6th Main Road (W0153)	Sqm	2	124.00	0.90		223.20		
					Total		**651.60**		
	Deduct 30% for Missing/Damaged						**195.48**		
	Consider 70% Qnty for Removing & Refixing						**456.12**		
	Basic rate	105.00							
	Area weightage 6%	6.3							
	Sub Total	**111.30**							
	Total						**550.62**	**111.30**	**61285.00**
3	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.(P.No.27,I.No.5.31.1)								
		From item no.1							
	Provide30% new BS Slab for Missing/Damaged	Sqm					**40.50**		
	Basic rate	700.00							
	Area weightage 6%	42							
	Sub Total	**742.00**							
	Total						**40.50**	**742.00**	**30051.00**
4	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.3)								
	For Drain								
	Palanahalli School Road (W0161)	Cum	2	156.00	1.10	0.15	51.48		
	Cross Road	Cum	2	95.00	1.10	0.15	31.35		
	For Culvert								
	Palanahalli School Road (W0161)	Cum	1	5.00	1.40	0.15	1.05		
		Cum	2	6.00	1.40	0.15	2.52		
	Basic rate	5301.69							
	Area weightage 6%	318.10							
	Sub Total	**5619.79**							
	Total						**86.40**	**5619.79**	**485550.00**

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
5	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM complete as per Specification-WALL & Bottom thickness 15Cm(Item No 37.59.2 page no 271)								
	Drain								
	Bottom Raft								
	Palanahalli School Road (W0161)	Cum	2	156.00	0.90	0.15	42.12		
	Cross Road	Cum	2	95.00	0.90	0.15	25.65		
	Side Wall								
	Palanahalli School Road (W0161)	Cum	4	156.00	0.15	0.60	56.16		
	Cross Road	Cum	4	95.00	0.15	0.60	34.20		
					Sub Total		**158.13**		
	Culvert								
	Bottom Raft								
	Palanahalli School Road (W0161)	Cum	1	5.00	1.20	0.20	1.20		
		Cum	2	6.00	1.20	0.20	2.88		
	Side Wall								
	Palanahalli School Road (W0161)	Cum	2	5.00	0.20	0.60	1.20		
		Cum	4	6.00	0.20	0.60	2.88		
					Sub Total		**8.16**		
	Basic rate	7002.82							
	Area weightage 6%	420.17							
	Sub Total	**7422.99**							
	Total						**166.29**	**7422.99**	**1234368.00**
6	KSRB M2200-6 Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200Specification No. Pg No.229 Item No.28.8.2								
	For Drain	Cum	From item no. 5				158.13		
		kg	Steel assumed 60Kg/Cum of Concrete				9487.80		
		tonne					**9.49**		
	For Culvert	Cum	From item no.5				8.16		
		kg	Steel assumed 90 Kg/Cum of Concrete				734.40		
		tonne					**0.73**		
	Basic rate	75610							
	Area weightage 6%	4536.6							
	Sub Total	**80146.60**							
	Total						**10.22**	**80146.60**	**819274.00**

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
7	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)								
	Provide30% Slab for Missing/Damaged	From item no.3					**195.48**		
	New Drain Cover slab								
	Palanahalli School Road (W0161)	Sqm	2	156.00	0.90		280.80		
	Cross Road	Sqm	2	95.00	0.90		171.00		
	Data rate	**1922.00**							
	Total						**647.28**	**1922.00**	**1244073.00**
8	Providing and Fixing pre cast **covering Slab 250mm thick** made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge								
	Culver cover Slab								
	Palanahalli School Road (W0161)	Sqm	1	5.00	1.20		6.00		
		Sqm	2	6.00	1.20		14.40		
	Data rate	**5418.00**							
	Total						**20.40**	**5418.00**	**110528.00**
9	KSRRB M300-14. **Excavation for roadwork in all types of soil** by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 5km lead= (I No-19.14,P No-143)								
	Road Cut Portion								
	Cross Road	Cum	1	520.00	1.30	0.20	135.20		
	Basic rate	41.00							
	Area weightage 6%	2.46							
	5Km lead= (2*1.28*5)	12.80							
	Sub Total	**56.26**							
	Total						**135.20**	**56.26**	**7607.00**
10	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications. MORTH / Chapter 3(P.No.146, I.No.19.56)								
	Anand Nagar								
	Cross Road-1 (W0101)	Sqm	1	100.00	5.20		520.00		
	1st Cross Road (W0097)	Sqm	1	90.00	5.50		495.00		
	Defence Layout Ph-1								
	8th Main Road (W0088)	Sqm	1	143.00	4.80		686.40		
	6th Main Road (W0153)	Sqm	1	124.00	5.20		644.80		
	Cross Road-1 (W0086)	Sqm	1	38.00	4.50		171.00		
	Cross Road-2 (WA088)	Sqm	1	34.00	4.40		149.60		
	Basic rate	39.00							

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	Area weightage 6%	2.34							
	Sub Total	**41.34**							
	Total						**2666.80**	**41.34**	**110245.00**
11	KSRRB 300-58. **Compaction of original ground** by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147)								
	Anand Nagar								
	Cross Road-1 (W0101)	Sqm	1	100.00	5.20		520.00		
	1st Cross Road (W0097)	Sqm	1	90.00	5.50		495.00		
	Defence Layout Ph-1								
	8th Main Road (W0088)	Sqm	1	143.00	4.80		686.40		
	6th Main Road (W0153)	Sqm	1	124.00	5.20		644.80		
	Cross Road-1 (W0086)	Sqm	1	38.00	4.50		171.00		
	Cross Road-2 (WA088)	Sqm	1	34.00	4.40		149.60		
	Basic rate	6.00							
	Area weightage 6%	0.36							
	Sub Total	**6.36**					**2666.80**	**6.36**	**16961.00**
	Total								
12	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	Road								
	Anand Nagar								
	Cross Road-1 (W0101)	Cum	1	100.00	5.20	0.20	104.00		
	1st Cross Road (W0097)	Cum	1	90.00	5.50	0.20	99.00		
	Defence Layout Ph-1								
	8th Main Road (W0088)	Cum	1	143.00	4.80	0.20	137.28		
	6th Main Road (W0153)	Cum	1	124.00	5.20	0.20	128.96		
	Cross Road-1 (W0086)	Cum	1	38.00	4.50	0.20	34.20		
	Cross Road-2 (WA088)	Cum	1	34.00	4.40	0.20	29.92		
	Road Cut Portion								
	Cross Road	Cum	1	520.00	1.30	0.20	135.20		
	Basic rate	1888.00							
	Area weightage 6%	113.28							
	Sub Total	**2001.28**					**668.56**	**2001.28**	**1337976.00**
	Total								
13	KSRRB M500-6. Providing and applying **primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6)								

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Anand Nagar								
	Cross Road-1 (W0101)	Sqm	1	100.00	5.20		520.00		
	1st Cross Road (W0097)	Sqm	1	90.00	5.50		495.00		
	Defence Layout Ph-1								
	8th Main Road (W0088)	Sqm	1	143.00	4.80		686.40		
	6th Main Road (W0153)	Sqm	1	124.00	5.20		644.80		
	Cross Road-1 (W0086)	Sqm	1	38.00	4.50		171.00		
	Cross Road-2 (WA088)	Sqm	1	34.00	4.40		149.60		
	Cross Road	Sqm	1	520.00	1.30		676.00		
	Basic rate	32.00							
	Area weightage 6%	1.92							
	Sub Total	**33.92**							
	Total						**3342.80**	**33.92**	**113388.00**
14	KSRRB 500-2.Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications.(P.No.158,I.No.21.2).								
	Cross Road	Sqm	1	520.00	5.50		2860.00		
	Basic rate	5.00							
	Area weightage 6%	0.3							
	Sub Total	**5.30**							
	Total						**2860.00**	**5.30**	**15158.00**
15	KSRRB 500-11. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 3.4 % VG-30 Bitumen(P.No.159,I.No.21.11.6).								
	Anand Nagar								
	Cross Road-1 (W0101)	Cum	1	100.00	5.20	0.05	26.00		
	1st Cross Road (W0097)	Cum	1	90.00	5.50	0.05	24.75		
	Defence Layout Ph-1								
	8th Main Road (W0088)	Cum	1	143.00	4.80	0.05	34.32		
	6th Main Road (W0153)	Cum	1	124.00	5.20	0.05	32.24		
	Cross Road-1 (W0086)	Cum	1	38.00	4.50	0.05	8.55		
	Cross Road-2 (WA088)	Cum	1	34.00	4.40	0.05	7.48		
	Cross Road	Cum	1	520.00	1.30	0.05	33.80		
	Basic rate	5533.00							
	Area weightage 6%	331.98							

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Sub Total	**5864.98**							
	Total						**167.14**	**5864.98**	**980272.00**
16	KSRRB 500-7. Providing and **applying tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7)								
	Anand Nagar								
	Cross Road-1 (W0101)	Sqm	1	100.00	5.20		520.00		
	1st Cross Road (W0097)	Sqm	1	90.00	5.50		495.00		
	Defence Layout Ph-1								
	8th Main Road (W0088)	Sqm	1	143.00	4.80		686.40		
	6th Main Road (W0153)	Sqm	1	124.00	5.20		644.80		
	Cross Road-1 (W0086)	Sqm	1	38.00	4.50		171.00		
	Cross Road-2 (WA088)	Sqm	1	34.00	4.40		149.60		
	Cross Road	Sqm	1	520.00	5.50		2860.00		
	Basic rate	12.00							
	Area weightage 6%	0.72							
	Sub Total	**12.72**							
	Total						**5526.80**	**12.72**	**70301.00**
17	KSRRB M500-19. Providing and laying **bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 507 of MORTH V revision using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-ll (30 mm to 45 mm) with 5.4% VG-30 Bitumen(P.No-162,I No-21.22.6)								
	Anand Nagar								
	Cross Road-1 (W0101)	Cum	1	100.00	5.20	0.04	20.80		
	1st Cross Road (W0097)	Cum	1	90.00	5.50	0.04	19.80		
	Defence Layout Ph-1								
	8th Main Road (W0088)	Cum	1	143.00	4.80	0.04	27.46		
	6th Main Road (W0153)	Cum	1	124.00	5.20	0.04	25.79		
	Cross Road-1 (W0086)	Cum	1	38.00	4.50	0.04	6.84		
	Cross Road-2 (WA088)	Cum	1	34.00	4.40	0.04	5.98		
	Cross Road	Cum	1	520.00	5.50	0.04	114.40		
	Basic rate	7972.00							
	Area weightage 6%	478.32							
	Sub Total	**8450.32**							
	Total						**221.07**	**8450.32**	**1868129.00**

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
18	KSRRB M800-13.**Road Marking with Hot Applied Thermoplastic Compound** with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)								
	Anand Nagar								
	Cross Road-1 (W0101)	Sqm	2	100.00	0.10		20.00		
	1st Cross Road (W0097)	Sqm	2	90.00	0.10		18.00		
	Defence Layout Ph-1								
	8th Main Road (W0088)	Sqm	2	143.00	0.10		28.60		
	6th Main Road (W0153)	Sqm	2	124.00	0.10		24.80		
	Cross Road-1 (W0086)	Sqm	2	38.00	0.10		7.60		
	Cross Road-2 (WA088)	Sqm	2	34.00	0.10		6.80		
	Cross Road	Sqm	2	520.00	0.10		104.00		
	Basic rate	429.00							
	Area weightage 6%	25.74							
	Sub Total	**454.74**							
	Total						**209.80**	**454.74**	**95404.00**
								Grand Total	**8749697.00**
								GST Charges (12% of estimated cost)	**1049963.00**
								DPR Charges (1% of estimated cost)	**100000.00**
								Project management And Consultancy Charges(1% of estimated cost)	**100000.00**
								Miscellenious and rounding	**340.00**
								Total Amount	**10000000.00**
								RUPEES ONE CRORE ONLY	

CERTIFICATE:

1) The work spot has been inspected and found to be necessary
2) The work spot comes under B.B.M.P
3) The provisions made in the estimate are necessary and minimum
4) The estimate is based on C.S.R of 2018-2019,Issue rates and Data Rates.

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

RUDRAPRASAD CONSULTANTS
BANGALORE

DETAILED ESTIMATE

For The Work Of

"Improvements And Restoration Of Roads At Srinivaspura Cross Roads, Bellahalli Roads And Other Roads In Ward No. 05 Byatarayanapura Sub Division"

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- IMPROVEMENTS AND RESTORATION OF ROADS AT SRINIVASPURA CROSS ROADS, BELLAHALLI ROADS AND OTHER ROADS IN WARD NO. 05 BYATARAYANAPURA SUB DIVISION

								Estimation Cost.Rs	**10000000.00**
Sl No	**Description of work**		**Mesurement**				**Qty**	**Rate**	**Amount**
		Unit	**No.**	**L**	**B**	**D**			
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80								
	For Culvert								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Cum	1	8.60	1.70	0.95	13.89		
		Cum	9	6.00	1.40	0.95	71.82		
	For Drain Desilt								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Cum	1	555.00	0.45	0.45	112.39		
	Basic rate	130.00							
	Area weightage 6%	7.80							
	5Km lead & Lift= 57+(2*1.28*5)	69.80							
	Sub Total	**207.60**							
	Total						**198.10**	**207.60**	**41125.00**
2	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.(P.No.27,I.No.5.31.1)								
	BS slab of Drain								
	Open Drain (Sides & Bottom)		Width=Perimeter of Drain in U Shape						
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Sqm	1	555.00	1.35		749.25		
	Basic rate	700.00							
	Area weightage 6%	42							
	Sub Total	**742.00**							
	Total						**749.25**	**742.00**	**555944.00**
3	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.3)								
	For Culvert								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Cum	1	8.60	1.70	0.15	2.19		
		Cum	9	6.00	1.40	0.15	11.34		
	Basic rate	5301.69							
	Area weightage 6%	318.10							
	Sub Total	**5619.79**							
	Total						**13.53**	**5619.79**	**76053.00**

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
4	Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification No. 1500, 1700, 2200. Including Cost of material, Labour, HOM complete as per Specification-WALL & Bottom thickness 15Cm(Item No 37.59.2 page no 271)								
	Culvert								
	Bottom Raft								
	Layout								
	Main Road to Arch (W0540)	Cum	1	8.60	1.50	0.20	2.58		
		Cum	9	6.00	1.20	0.20	12.96		
	Side Wall								
	Main Road to Arch (W0540)	Cum	2	8.60	0.20	0.60	2.06		
		Cum	18	6.00	0.20	0.60	12.96		
						Sub Total	**30.56**		
	Basic rate	7002.82							
	Area weightage 6%	420.17							
	Sub Total	**7422.99**					**30.56**	**7422.99**	**226877.00**
	Total								
5	KSRB M2200-6 Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200Specification No. Pg No.229 Item No.28.8.2								
	For Culvert	Cum	From item no.4				30.56		
		kg	Steel assumed 90 Kg/Cum of Concrete				2750.76		
		tonne					**2.75**		
		tonne							
	Basic rate	75610							
	Area weightage 6%	4536.6							
	Sub Total	**80146.60**					**2.75**	**80146.60**	**220465.00**
	Total								
6	Providing and Fixing pre cast **covering Slab 250mm thick** made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge								
	Culver cover Slab								
	Vidhanasoudha								
	Layout								
	Main Road to Arch (W0540)	Cum	1	8.60	1.50		12.90		
		Cum	9	6.00	1.20		64.80		
	Data rate	**5418.00**							
	Total						**77.70**	**5418.00**	**420978.00**
7	KSRRB M300-14. **Excavation for roadwork in all types of soil** by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 5km lead= (I No-19.14,P No-143)								
	Cut Portion								
	Vidhanasoudha								
	Layout								
	Arch to Dead End (W0504)	Cum	1	10.00	2.00	0.20	4.00		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
		Cum	1	15.00	0.60	0.20	1.80		
		Cum	1	10.00	1.50	0.20	3.00		
		Cum	1	25.00	1.00	0.20	5.00		
		Cum	1	25.00	1.00	0.20	5.00		
	Road Cut Portion								
	Water Supply Line								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Cum	1	555.00	1.20	0.60	399.60		
	Arch to Dead End (W0504)	Cum	1	485.00	1.20	0.60	349.20		
	Basic rate	41.00							
	Area weightage 6%	2.46							
	5Km lead= (2*1.28*5)	12.80							
	Sub Total	**56.26**					**767.60**	**56.26**	**43186.00**
	Total								
8	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications. MORTH / Chapter 3(P.No.146, I.No.19.56)								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Sqm	1	555.00	7.20		3996.00		
	Basic rate	39.00							
	Area weightage 6%	2.34							
	Sub Total	**41.34**					**3996.00**	**41.34**	**165195.00**
	Total								
9	Supplying and laying Sand / Crushed Sand (Page No III Sl. No. 51 PWD SR 2018-2019)								
	Road Cut Portion								
	Water Supply Line								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Cum	1	555.00	1.20	0.30	199.80		
	Arch to Dead End (W0504)	Cum	1	485.00	1.20	0.30	174.60		
	Basic rate	**1680.95**							
	Total						**374.40**	**1680.95**	**629348.00**
10	KSRRB 300-64.1. Extra for watering the earth to bring the earth upto required optimum moisture content manually including cost of all labour complete as per specifications. (Page No. 148/ Item No. 19.71 PWD SR 2018-19)								
	Road Cut Portion								
	Water Supply Line								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Cum	1	555.00	1.20	0.30	199.80		
	Arch to Dead End (W0504)	Cum	1	485.00	1.20	0.30	174.60		
	Basic rate	12.00							
	Area weightage 6%	0.72							
	Sub Total	**12.72**					**374.40**	**12.72**	**4763.00**
	Total								

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
11	KSRRB 300-58. **Compaction of original ground** by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147)								
	Road								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Sqm	1	555.00	7.20		3996.00		
	Basic rate	6.00							
	Area weightage 6%	0.36							
	Sub Total	**6.36**							
	Total						**3996.00**	**6.36**	**25415.00**
12	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	Road								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Cum	1	555.00	7.20	0.20	799.20		
	Road Cut Portion								
	Water Supply Line								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Cum	1	555.00	1.20	0.25	166.50		
	Arch to Dead End (W0504)	Cum	1	485.00	1.20	0.25	145.50		
	Cut Portion								
	Arch to Dead End (W0504)	Cum	1	10.00	2.00	0.20	4.00		
		Cum	1	15.00	0.60	0.20	1.80		
		Cum	1	10.00	1.50	0.20	3.00		
		Cum	1	25.00	1.00	0.20	5.00		
		Cum	1	25.00	1.00	0.20	5.00		
	Basic rate	1888.00							
	Area weightage 6%	113.28							
	Sub Total	**2001.28**							
	Total						**1130.00**	**2001.28**	**2261447.00**
13	KSRRB M500-6. Providing and applying **primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6)								
	Road								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Sqm	1	555.00	7.20		3996.00		
	Road Cut Portion								
	Vidhanasoudha Layout								
	Arch to Dead End (W0504)	Sqm	1	10.00	2.00		20.00		
		Sqm	1	15.00	0.60		9.00		
		Sqm	1	10.00	1.50		15.00		
		Sqm	1	25.00	1.00		25.00		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
		Sqm	1	25.00	1.00		25.00		
	Basic rate	32.00							
	Area weightage 6%	1.92							
	Sub Total	**33.92**							
	Total						**4090.00**	**33.92**	**138732.00**
14	KSRRB 500-2.Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications.(P.No.158,I.No.21.2).								
	Road								
	Vidhanasoudha Layout								
	Arch to Dead End (W0504)	Sqm	1	485.00	7.20		3492.00		
	Basic rate	5.00							
	Area weightage 6%	0.3							
	Sub Total	**5.30**							
	Total						**3492.00**	**5.30**	**18508.00**

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
15	KSRRB 500-11. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 3.4 % VG-30 Bitumen(P.No.159,I.No.21.11.6).								
	Road								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Cum	1	555.00	7.20	0.05	199.80		
	Road Cut Portion								
	Vidhanasoudha Layout								
	Arch to Dead End (W0504)	Cum	1	10.00	2.00	0.05	1.00		
		Cum	1	15.00	0.60	0.05	0.45		
		Cum	1	10.00	1.50	0.05	0.75		
		Cum	1	25.00	1.00	0.05	1.25		
		Cum	1	25.00	1.00	0.05	1.25		
	Basic rate	5533.00							
	Area weightage 6%	331.98							
	Sub Total	**5864.98**							
	Total						**204.50**	**5864.98**	**1199388.00**
16	KSRRB 500-7. Providing and **applying tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7)								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Sqm	1	555.00	7.20		3996.00		
	Arch to Dead End (W0504)	Sqm	1	485.00	7.20		3492.00		
	Basic rate	12.00							
	Area weightage 6%	0.72							
	Sub Total	**12.72**							
	Total						**7488.00**	**12.72**	**95247.00**
17	KSRRB M500-19. Providing and laying **bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 507 of MORTH V revision using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-ll (30 mm to 45 mm) with 5.4% VG-30 Bitumen(P.No-162,I No-21.22.6)								
	Road								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Cum	1	555.00	7.20	0.04	159.84		
	Arch to Dead End (W0504)	Cum	1	485.00	7.20	0.04	139.68		
	Basic rate	7972.00							
	Area weightage 6%	478.32							
	Sub Total	**8450.32**							
	Total						**299.52**	**8450.32**	**2531039.00**

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
18	KSRRB M800-13.**Road Marking with Hot Applied Thermoplastic Compound** with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)								
	Road								
	Vidhanasoudha Layout								
	Main Road to Arch (W0540)	Sqm	2	555.00	0.10		111.00		
	Arch to Dead End (W0504)	Sqm	2	485.00	0.10		97.00		
	Basic rate	429.00							
	Area weightage 6%	25.74							
	Sub Total	**454.74**							
	Total						**208.00**	**454.74**	**94585.00**
								Grand Total	**8748295.00**
								GST Charges (12% of estimated cost)	**1049796.00**
								DPR Charges (1% of estimated cost)	**100000.00**
								Project management And Consultancy Charges(1% of estimated cost)	**100000.00**
								Miscellenious and rounding	**1909.00**
								Total Amount	**10000000.00**
								RUPEES ONE CRORE ONLY	

CERTIFICATE:

1) The work spot has been inspected and found to be necessary
2) The work spot comes under B.B.M.P
3) The provisions made in the estimate are necessary and minimum
4) The estimate is based on C.S.R of 2018-2019,Issue rates and Data Rates.

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

RUDRAPRASAD CONSULTANTS BANGALORE

DETAILED ESTIMATE

For the Work of

"Improvements And Restoration Of Roads At Sampigehalli Srirampura And Jakkur Surrounding Area And Other Roads In Ward No. 05 Byatarayanapura Sub Division"

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- IMPROVEMENTS AND RESTORATION OF ROADS AT SAMPIGEHALLI SRIRAMPURA AND JAKKUR SURROUNDING AREA AND OTHER ROADS IN WARD NO. 05 BYATARAYANAPURA SUB DIVISION

									Estimation Cost.Rs	**10000000.00**
Sl No	**Description of work**		**Mesurement**				**Qty**	**Rate**	**Amount**
		Unit	**No.**	**L**	**B**	**D**			
1	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 5km lead= 57+2.0x1.28x5 =69.80								
	Road								
	Over Burden								
	Central Exchange Layout								
	Road-#135/A (W1951)	Cum	2	138.00	0.60	0.30	49.68		
	Drain Desilting								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	5th Cross Road (W1941)	Cum	2	196.00	0.60	0.60	141.12		
	6th Cross Road (W1935)	Cum	2	189.00	0.60	0.60	136.08		
	Central Exchange Layout								
	Sumbrodi House Road-#135/A (W1951)	Cum	2	138.00	0.60	0.60	99.36		
	1st Cross Road (W1160)	Cum	2	238.00	0.60	0.60	171.36		
	2nd Cross Road (W1152)	Cum	2	201.00	0.60	0.60	144.72		
	White Pearl Apartment (W1078)	Cum	2	120.70	0.60	0.60	86.90		
	S.K.W Club Road (W1096)	Cum	2	421.00	0.45	0.45	170.51		
	Basic rate	130.00							
	Area weightage 6%	7.80							
	5Km lead & Lift= 57+(2*1.28*5)	69.80							
	Sub Total	**207.60**							
	Total						**999.73**	**207.60**	**207544.00**
2	**Removing and refixing** stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33)								
	BS slab of Drain								
	Open Drain (Sides & Bottom)		Width=Perimeter of Drain in U Shape						
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	5th Cross Road (W1941)	Sqm	2	196.00	1.80		705.60		
	6th Cross Road (W1935)	Sqm	2	189.00	1.80		680.40		

Sl No	Description of work	Unit	Mesurement No.	L	B	D	Qty	Rate	Amount
	Central Exchange Layout								
	Sumbrodi House Road-#135/A (W1951)	Sqm	2	138.00	1.80		496.80		
	1st Cross Road (W1160)	Sqm	2	238.00	1.80		856.80		
	2nd Cross Road (W1152)	Sqm	2	201.00	1.80		723.60		
	White Pearl Apartment (W1078)	Sqm	2	120.70	1.80		434.52		
	S.K.W Club Road (W1096)	Sqm	2	421.00	1.35		1136.70		
						Total	**5034.42**		
	Deduct 30% for Missing/Damaged						**1510.33**		
	Consider 70% Qnty for Removing & Refixing						**3524.09**		
	Basic rate	105.00							
	Area weightage 6%	6.3							
	Sub Total	**111.30**							
	Total						**3524.09**	**111.30**	**392232.00**
3	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.(P.No.27,I.No.5.31.1)								
		Sqm							
	Provide30% new BS Slab for Missing/Damaged	From item no.2					**1510.33**		
	Basic rate	700.00							
	Area weightage 6%	42							
	Sub Total	**742.00**							
	Total						**1510.33**	**742.00**	**1120662.00**
4	KSRRB M300-14. **Excavation for roadwork in all types of soil** by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 5km lead= (I No-19.14,P No-143)								
	Road Cut Portion								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	5th Cross Road (W1941)	Cum	1	196.00	0.60	0.20	23.52		
		Cum	1	20.00	2.00	0.20	8.00		
		Cum	1	15.00	1.00	0.20	3.00		
		Cum	1	25.00	0.60	0.20	3.00		
	Central Exchange Layout								
	Sumbrodi House Road-#135/A (W1951)	Cum	1	15.00	0.60	0.20	1.80		
		Cum	1	10.00	4.40	0.20	8.80		
		Cum	1	1.00	2.00	0.20	0.40		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
		Cum	1	5.00	2.00	0.20	2.00		
	S.K.W Club Road (W1096)	Cum	1	421.00	1.20	0.20	101.04		
		Cum	1	421.00	0.60	0.20	50.52		
		Cum	1	10.00	0.60	0.20	1.20		
		Cum	1	15.00	0.10	0.20	0.30		
	Cut Portion								
	1st Cross Road (W1160)	Cum	1	10.00	0.60	0.20	1.20		
		Cum	1	15.00	1.00	0.20	3.00		
		Cum	1	18.00	1.50	0.20	5.40		
	2nd Cross Road (W1152)	Cum	1	10.00	2.00	0.20	4.00		
		Cum	1	15.00	1.50	0.20	4.50		
		Cum	1	10.00	0.60	0.20	1.20		
	Road Widening								
	1st Cross Road (W1160)	Cum	2	238.00	0.60	0.20	57.12		
	2nd Cross Road (W1152)	Cum	2	201.00	0.60	0.20	48.24		
	Basic rate	41.00							
	Area weightage 6%	2.46							
	5Km lead= (2*1.28*5)	12.80							
	Sub Total	**56.26**							
	Total						**328.24**	**56.26**	**18467.00**
5	KSRRB 300-50. Scarifying bituminous course 50mm to 75mm thick along with premix carpet / surface dressing by road roller attached with scarifier without disturbing the base and stacking the debris including cost of all labour charges, HOM of machineries complete as per specifications. MORTH / Chapter 3(P.No.146, I.No.19.56)								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	6th Cross Road (W1935)	Sqm	1	189.00	6.40		1209.60		
	Central Exchange Layout								
	White Pearl Apartment (W1078)	Sqm	1	120.70	7.10		856.97		
	Basic rate	39.00							
	Area weightage 6%	2.34							
	Sub Total	**41.34**							
	Total						**2066.57**	**41.34**	**85433.00**
6	KSRRB 300-58. **Compaction of original ground** by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147)								
	Road								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	6th Cross Road (W1935)	Sqm	1	189.00	6.40		1209.60		
	Central Exchange Layout								

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	White Pearl Apartment (W1078)	Sqm	1	120.70	7.10		856.97		
	Basic rate	6.00							
	Area weightage 6%	0.36							
	Sub Total	**6.36**							
	Total						**2066.57**	**6.36**	**13144.00**
7	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to **wet mix macadam** specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	Road								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	6th Cross Road (W1935)	Cum	1	189.00	6.40	0.20	241.92		
	Central Exchange Layout								
	White Pearl Apartment (W1078)	Cum	1	120.70	7.10	0.20	171.39		
	Road Cut Portion								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	5th Cross Road (W1941)	Cum	1	196.00	0.60	0.20	23.52		
		Cum	1	20.00	2.00	0.20	8.00		
		Cum	1	15.00	1.00	0.20	3.00		
		Cum	1	25.00	0.60	0.20	3.00		
	Central Exchange Layout								
	Sumbrodi House Road-#135/A (W1951)	Cum	1	15.00	0.60	0.20	1.80		
		Cum	1	10.00	4.40	0.20	8.80		
		Cum	1	1.00	2.00	0.20	0.40		
		Cum	1	5.00	2.00	0.20	2.00		
	S.K.W Club Road (W1096)	Cum	1	421.00	1.20	0.20	101.04		
		Cum	1	421.00	0.60	0.20	50.52		
		Cum	1	10.00	0.60	0.20	1.20		
		Cum	1	15.00	0.10	0.20	0.30		
	Cut Portion								
	1st Cross Road (W1160)	Cum	1	10.00	0.60	0.20	1.20		
		Cum	1	15.00	1.00	0.20	3.00		
		Cum	1	18.00	1.50	0.20	5.40		
	2nd Cross Road (W1152)	Cum	1	10.00	2.00	0.20	4.00		
		Cum	1	15.00	1.50	0.20	4.50		
		Cum	1	10.00	0.60	0.20	1.20		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	Road Widening								
	1st Cross Road (W1160)	Cum	2	238.00	0.60	0.20	57.12		
	2nd Cross Road (W1152)	Cum	2	201.00	0.60	0.20	48.24		
	Basic rate	1888.00							
	Area weightage 6%	113.28							
	Sub Total	**2001.28**							
	Total						**741.55**	**2001.28**	**1484058.00**
8	KSRRB M500-6. Providing and applying **primer coat** with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6)								
	Road								
	White Pearl Apartment (W1078)	Sqm	1	120.70	7.10		856.97		
	6th Cross Road (W1935)	Sqm	1	189.00	6.40		1209.60		
	Road Cut Portion								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	5th Cross Road (W1941)	Sqm	1	196.00	0.60		117.60		
		Sqm	1	20.00	2.00		40.00		
		Sqm	1	15.00	1.00		15.00		
		Sqm	1	25.00	0.60		15.00		
	Central Exchange Layout								
	Sumbrodi House Road-#135/A (W1951)	Sqm	1	15.00	0.60		9.00		
		Sqm	1	10.00	4.40		44.00		
		Sqm	1	1.00	2.00		2.00		
		Sqm	1	5.00	2.00		10.00		
	S.K.W Club Road (W1096)	Cum	1	421.00	1.20		505.20		
		Cum	1	421.00	0.60		252.60		
		Sqm	1	10.00	0.60		6.00		
		Sqm	1	15.00	0.10		1.50		
	Cut Portion								
	1st Cross Road (W1160)	Sqm	1	10.00	0.60		6.00		
		Sqm	1	15.00	1.00		15.00		
		Sqm	1	18.00	1.50		27.00		
	2nd Cross Road (W1152)	Sqm	1	10.00	2.00		20.00		
		Sqm	1	15.00	1.50		22.50		
		Sqm	1	10.00	0.60		6.00		
	Basic rate	32.00							
	Area weightage 6%	1.92							
	Sub Total	**33.92**							
	Total						**3180.97**	**33.92**	**107898.00**

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
9	KSRRB 500-2.Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications.(P.No.158,I.No.21.2).								
	Road Cut Portion								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	5th Cross Road (W1941)	Sqm	1	196.00	8.80		1724.80		
	Central Exchange Layout								
	Sumbrodi House Road-#135/A (W1951)	Sqm	1	138.00	8.30		1145.40		
	1st Cross Road (W1160)	Sqm	1	238.00	8.30		1975.40		
	2nd Cross Road (W1152)	Sqm	1	201.00	8.40		1688.40		
	S.K.W Club Road (W1096)	Sqm	1	421.00	8.00		3368.00		
	Basic rate	5.00							
	Area weightage 6%	0.3							
	Sub Total	**5.30**							
	Total						**9902.00**	**5.30**	**52480.00**
10	KSRRB 500-11. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications. MORTH /Chapter 5 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 3.4 % VG-30 Bitumen(P.No.159,I.No.21.11.6).								
	Road								
	White Pearl Apartment (W1078)	Cum	1	120.70	7.10	0.05	42.85		
	6th Cross Road (W1935)	Cum	1	189.00	6.40	0.05	60.48		
	Road Cut Portion								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	5th Cross Road (W1941)	Cum	1	196.00	0.60	0.05	5.88		
		Cum	1	20.00	2.00	0.05	2.00		
		Cum	1	15.00	1.00	0.05	0.75		
		Cum	1	25.00	0.60	0.05	0.75		
	Central Exchange Layout								
	Sumbrodi House Road-#135/A (W1951)	Cum	1	15.00	0.60	0.05	0.45		
		Cum	1	10.00	4.40	0.05	2.20		
		Cum	1	1.00	2.00	0.05	0.10		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
		Cum	1	5.00	2.00	0.05	0.50		
	S.K.W Club Road (W1096)	Cum	1	421.00	1.20	0.05	25.26		
		Cum	1	421.00	0.60	0.05	12.63		
		Cum	1	10.00	0.60	0.05	0.30		
		Cum	1	15.00	0.10	0.05	0.08		
	Cut Portion								
	1st Cross Road (W1160)	Cum	1	10.00	0.60	0.05	0.30		
		Cum	1	15.00	1.00	0.05	0.75		
		Cum	1	18.00	1.50	0.05	1.35		
	2nd Cross Road (W1152)	Cum	1	10.00	2.00	0.05	1.00		
		Cum	1	15.00	1.50	0.05	1.13		
		Cum	1	10.00	0.60	0.05	0.30		
	Basic rate	5533.00							
	Area weightage 6%	331.98							
	Sub Total	**5864.98**							
	Total						**159.05**	**5864.98**	**932816.00**
11	KSRRB 500-7. Providing and **applying tack coat** using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7)								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	5th Cross Road (W1941)	Sqm	1	196.00	8.80		1724.80		
	6th Cross Road (W1935)	Sqm	1	189.00	6.40		1209.60		
	Central Exchange Layout								
	Sumbrodi House Road-#135/A (W1951)	Sqm	1	138.00	8.30		1145.40		
	1st Cross Road (W1160)	Sqm	1	238.00	8.30		1975.40		
	2nd Cross Road (W1152)	Sqm	1	201.00	8.40		1688.40		
	White Pearl Apartment (W1078)	Sqm	1	120.70	7.10		856.97		
	S.K.W Club Road (W1096)	Sqm	1	421.00	8.00		3368.00		
	Basic rate	12.00							
	Area weightage 6%	0.72							
	Sub Total	**12.72**							
	Total						**11968.57**	**12.72**	**152240.00**

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
12	KSRRB M500-19. Providing and laying **bituminous concrete** using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 507 of MORTH V revision using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-ll (30 mm to 45 mm) with 5.4% VG-30 Bitumen(P.No-162,I No-21.22.6)								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	5th Cross Road (W1941)	Cum	1	196.00	8.80	0.04	68.99		
	6th Cross Road (W1935)	Cum	1	189.00	6.40	0.04	48.38		
	Central Exchange Layout								
	Sumbrodi House Road-#135/A (W1951)	Cum	1	138.00	8.30	0.04	45.82		
	1st Cross Road (W1160)	Cum	1	238.00	8.30	0.04	79.02		
	2nd Cross Road (W1152)	Cum	1	201.00	8.40	0.04	67.54		
	White Pearl Apartment (W1078)	Cum	1	120.70	7.10	0.04	34.28		
	S.K.W Club Road (W1096)	Cum	1	421.00	8.00	0.04	134.72		
	Basic rate	7972.00							
	Area weightage 6%	478.32							
	Sub Total	**8450.32**							
	Total						**478.74**	**8450.32**	**4045529.00**
13	KSRRB M800-13.**Road Marking with Hot Applied Thermoplastic Compound** with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)								
	Sampigehalli & Sri Rampura								
	Winn Field Garden								
	5th Cross Road (W1941)	Sqm	2	196.00	0.10		39.20		
	6th Cross Road (W1935)	Sqm	2	189.00	0.10		37.80		
	Central Exchange Layout	Sqm							
	Sumbrodi House Road-#135/A (W1951)	Sqm	2	138.00	0.10		27.60		
	1st Cross Road (W1160)	Sqm	2	238.00	0.10		47.60		
	2nd Cross Road (W1152)	Sqm	2	201.00	0.10		40.20		
	White Pearl Apartment (W1078)	Sqm	2	120.70	0.10		24.14		

Sl No	Description of work	Unit	Mesurement				Qty	Rate	Amount
			No.	L	B	D			
	S.K.W Club Road (W1096)	Sqm	2	421.00	0.10		84.20		
	Basic rate	429.00							
	Area weightage 6%	25.74							
	Sub Total	**454.74**							
	Total						**300.74**	**454.74**	**136758.00**
								Total Amount	**8749261.00**
								DPR Charges (1% of estimated cost)	**100000.00**
								Project management And Consultancy Charges(1% of estimated cost)	**100000.00**
								GST Charges (12% of estimated cost)	**1049911.00**
								Miscellenious and rounding	**828.00**
								Total Amount	**10000000.00**
									RUPEES ONE CRORE ONLY

CERTIFICATE:

1) The work spot has been inspected and found to be necessary
2) The work spot comes under B.B.M.P
3) The provisions made in the estimate are necessary and minimum
4) The estimate is based on C.S.R of 2018-2019,Issue rates and Data Rates.

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

RUDRAPRASAD CONSULTANTS
BANGALORE